



Sanitary Installation	MEIKO	In the building
B Cold water	R 1/2" NPT, Stop cocks, 'y' Strainer	Inset pipe 3/4", 41"-77"
C Hot water	R 1/2" NPT, Stop cocks, 'y' Strainer	Inset pipe 3/4", Stop-cocks, 100"-140"
E Waste Outlet	3" P-trap	Waste Pipe 3" DU 4
F Vent	2" Vent Connection	Local Area Vent 2" 12.4 CFM

Electrical Installation
 A 3 PH ~ 208/230V, 60Hz, 4.2kW/4.6kVA
 Protection class Equipment I, Pollution Degree 2, Installation Category II, Main switch, to the local and national power utilities regulations.
 Connection dimensions are subject to tolerances. It is neither allowed to give this drawing without our permission to a third party for information or reproduction, nor may it be used for competition purposes. All rights are reserved. Subject to technical changes.

MEIKO USA INC.
 1349 Heil Daker Blvd Laverne TN 37085
 UNITED STATES OF AMERICA
 TEL: (615)399-6600 FAX: (615)399-6600

Reference: Type: TDP1 INC 30 DT -NDV LH
 Thermal disinfection/Intermittent Steam Generation
 Proj. no. _____
 Drawing no. _____
 Index _____



Weight of frame 30 kg - 66 lbs.
 Weight of unit 80 kg - 176 lbs.
 Total weight 110 kg - 242 lbs.



Note: See DPA-2522-10

Note: See DPA-2522-10

FRR US INSTALLATION ONLY