

Technical data sheet

UPster U 400

Execution for: Hong Kong

Glass and dishwasher

3-phase current: 3N PE 400V 50Hz

Fresh water line: Soft cold water 0-3 °dH



Sample illustration

Technical data

Rack capacity/h (theoretical)	30 / 20 / 15 racks/h
Programme cycle time *	120 / 180 / 240 s (glass / dish / dish intensive)
Rack dimension	400 x 400 mm
Entry height	300 mm
Dimensions (W x Hmin x D)	460 x 700 x 600 mm
Electrical feeding cable	3-phase current 3N PE 400V 50Hz* nominal capacity: 3.8 kW max. rated current: 13.4 A
Local fuse protection	16 A
Protection class of the machine	IP X4
Equipment	MIKE control Infrared interface for wireless communication Soft start Drain pump Boiler safety device Automatic self-cleaning when tank is drained
Fresh water supply	Minimum flow pressure 250 kPa / 2.5 bar in front of solenoid valve Maximum pressure: 500 kPa / 5.0 bar Max. supply water temperature 60 °C
Flow rate	min. 0.22 l/s at 250 kPa/2.5 bar flow pressure
Final rinse water quantity	2.2 liters/cycle
Boiler	Contents: 4.2 l Heater: 3.00 kW Temperature: 65 °C, with dish wash programme 83 °C Tank / boiler locked

Technical data sheet

Wash tank	Filling: 11 l Heater: 2.00 kW Temperature: 60 °C
Wash pump	Performance: 0.55 kW
Dosing of rinse aid	Hose pump (24 V) with time control and suction lance
Detergent dosage	Hose pump (24 V) with time control and suction lance
Material	Cladding: 1.4301 Wash tank: 1.4301 Boiler: 1.4404
Heat emission	for 15 programme cycles/h total: 1.0 kW perceptible: 0.7 kW latent: 0.3 kW
Ventilation flow rate	250 m ³ /h
Steam emission	0.5 kg/h
Emission sound pressure level at the workplace (LpA)	62 dB
Net / gross weight	45.0 kg / 54.0 kg (standard packaging)
Packaging dimensions (W x H x D)	560 x 900 x 690 mm (standard packaging)

*Note:

Electrical equipment suitable for supply voltage:

3N PE 400 V 50 HZ (3N PE 380-415 V 50 Hz)

1N PE 230 V 50 HZ (1N PE 220-240 V 50 Hz)

* Programme cycle time depending on temperature of feeding water:

Prolongation of wash cycle with cold water connection or single phase execution;

For machine with single phase connection, hot water connection is recommended.